

Government Tender Notice

Invitation of Tender Notice Nos. **97, 98 & 100/Seri/Eng/Civil/PCR/NAD/2019-20**.

Sealed Tenders are invited by the Executive Engineer, Sericulture, West Bengal, 45, Ganesh Chandra Avenue, (2nd floor), Kolkata-13 for the following works in the district of Nadia from the bonafide experienced and resourceful contractors having experienced in such type of works in pure Govt. Department / Zilla Parishad.

NIT	Name of the Work	Estimated Cost	Earnest Money	Place of Work.	Time of completion
97	Repairing of 2-Storeyed Grainage Building (G.F.) at Ranaghat Sericulture Complex, Nadia under PCR.	Rs.4,97,222.00 (Rupees Four Lakh Ninety Seven thousand Two hundred Twenty)only	Rs12,435.00 (Rupees Twelve Thousand Four Hundred Thirty Five) only.	Ranaghat Sericulture Complex, Nadia.	1 (One) month from the date of issue of Work Order.
98	Renovation of boundary wall and drainage System of field at Shibnibas Sericulture Farm, Nadia under P.C.R. works.	Rs. 2,95,573.00 (Rupees Two lakhs ninety five thousand Five Hundred Seventy Three)only.	Rs. 7390.00 (Rupees Seven thousand three hundred Ninety) Only	Shibnibas Sericulture Farm, Nadia.	
100	Construction of Boundary Wall with partly vertical extension of boundary wall at Ranaghat Sericulture Farm, Nadia under P.C.R.	Rs.4,97,586.00 (Rupees Four lakh Ninety Seven Thousand Five Hundred Eighty Six)only.	Rs.12,440.00/- (Rupees Twelve Thousand Four Hundred Forty) only.	Ranaghat Sericulture Farm, Nadia.	

Tender papers (NIT), Priced Schedule & Form-2911(ii) etc. may be obtained/downloaded from seriwb.gov.org at free of cost.

Last date & time of submission of Tender	28.01-2020 upto 3-00 P.M. at Head Quarters, Kolkata.
Date & time of opening of Tender	28.01.2020 upto 3-30 P.M. at Head Quarters, Kolkata.

Tender should be submitted / dropped in the box kept at Head Quarters, Kolkata and papers should be arranged in the following manner.

Envelop - I, should be superscribed as Technical Bid for N.I.T No.....SL No. of Work, Name of agency and it should contain (Self Attested) PAN Card, Last I.T. Return, valid GSTIN Registration, P.Tax Challan, Credential (similar nature of work at about 60% of Tender Value) EMD & etc. and sealed.

Envelop - II, should be super scribed as Financial Bid for N.I.T. No..... SL No. of Work, Name of Agency and should contain filled in - **2911 (ii)** quoting the Rate and Sealed.


2(two) envelopes as noted above (I & II) should be put in a bigger envelop and sealed. Agency should write clearly N.I.T. No., Name of Work, SL.No. and Name of the Agency on this Envelope and drop the same as per schedule mentioned in this N.I.T.

Technical Bid will be opened first. Financial Bid will be opened only if the technical Bid is found acceptable.

Labour Cess will be deducted from bill value as per Govt. Rules. All original copies are to be shown for verification. The details may be seen in the Office of the **Commissioner of Textiles (Sericulture), West Bengal**, 45, Ganesh Ch, Avenue (2nd floor), Kolkata-13 on any working days and web site seriwb.gov.org. The **Commissioner of Textiles (Sericulture), West Bengal** reserves the right to reject/cancel all the applications without showing any reasons thereof. If any date as above happens to be holidays the next working days will be considered as stipulated date. Acceptance of lowest tender is not obligatory.

N.S.C./ K.V.P. will not be accepted as Earnest Money. Only the Bank Draft of a Nationalised Bank will be considered as Earnest money. Acceptance of lowest Tender is not obligatory.

Notwithstanding anytime contained in this Notice Inviting Tender, the other terms & conditions and special terms & conditions will remain binding upon all concerned.


Executive Engineer,
Directorate of Sericulture,
West Bengal.

Priced schedule for construction of boundary wall with partly vertical extension of existing boundary wall at Ranaghat Sericulture Complex, Ranaghat, Nadia under P.C.R. during 2019-20.

Sl.No.	Description of item	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
1.	Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete. Depth of excavation not exceeding 1,500 mm	19.00	Cum.	119.27	2,266.00
2.	Single Brick Flat Soling of picked jhama Bricks including ramming and dressing bed to proper level and filling joints with local sand.	27.00	Sqm	325.00	8,775.00
3.	Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. (i) Pakur Variety.	2.70	Cum	5,806.44	15,677.00
4.	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc. initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. For works in foundation, basement and up to roof of ground floor / up to 4m. I) Tor steel/Mild steel	0.65	M.T.	68,053.00	4,4234.00
5.	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. I) Pakur Variety.	8.00	Cum.	6,116.00	48,928.00
6.	Hire and labour charges for shuttering with cantering and necessary staging up to 4 m. using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams, columns, lintels curved or straight including fitting, fixing and striking out after completion of works. (up to roof of ground floor) 25 mm. to 30 mm. thick wooden shuttering as per decision & direction of Engineer-in-charge.	80.00	Sqm.	330.00	26,400.00
7.	125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor.	162.00	Sqm	679.00	1,09,998.00
8.	Brick work with 1st class bricks in cement mortar (4:1).a) In foundation and plinth.	1.00	Cum.	5,220.00	5,220.00
9.	Brick work with 1st class bricks in cement mortar (4:1).a) In Superstructure G.F.	5.00	Cum	5,378.00	26,890.00
10.	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course scaffolding/staging where necessary (ground floor). [Excluding cost of chipping over concrete surface] With 1:4 cement mortar 20 mm. thick plaster	225.00	Sqm	184.00	41,400.00
11.	With 1:4 cement mortar 15 mm. thick plaster	225.00	Sqm.	159.00	35,775.00

12.	Applying Exterior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive decorative textured (matt finish) or smooth finish acrylic exterior emulsion paint including scraping and preparing the surface thoroughly complete as per manufacturer's specification and as per direction of the EIC. A) One coat.	648.00	Sqm	31.40	20,347.00
13.	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of EIC to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer. A) Premium 100% Acrylic Emulsion	684.00	Sqm.	84.00	54,432.00

TOTAL=Rs.4, 40,342.00

Add G.S.T. @ 12 % (+) =Rs. 52,841.00

Add Labour welfare cess @ 1% (+) =Rs. 4,403.00

TOTAL=Rs.4, 97,586.00

SY 23/1/19
Executive Engineer
Directorate of Textiles (Sericulture)
Government of West Bengal