

Government Tender Notice

Invitation of Tender Notice No.21,22 & 23/Seri/Eng/Civil/PCR/SCH/2017-'18.

Sealed Tenders are invited by the Executive Engineer, Textiles(Sericulture), West Bengal, 45, Ganesh Chandra Avenue,(2nd floor),Kolkata-13 for the following works at Silk Conditioning House, Lake Town, Kolkata -89 under P.C.R. from the bonafide experienced & resourceful contractors having experienced in such type of works in pure Govt. Department/Zilla Parishad.

Sl. No.	Name of the Work	Estimated Cost	Earnest money	Last date & time of Submission of Tender	Date of opening of Tender	Place of Work.	Time of Completion of work.
1.	Renovation of existing reservoir & pipe line at the Office & Staff Qtrs. of the Joint Director of Textiles (Sericulture), East Zone, Lake Town, Kolkata-89.	Rs.2,78,104/- (Rupees two lakh seventy eight thousand one hundred four) only.	Rs.6,955/- (Rupees six thousand nine hundred fifty five) only.	28.11.2017 upto 3-00 P.M. at H.Q., Kolkata.	28.11.2017 at 3-30 P.M. at H.Q. Kolkata	Silk Conditioning House, Lake Town, Kolkata-89.	1 (one) month from the date of issue of Work Order.
2.	Vertical Extension with M.S. Grill over existing boundry wall at Office campus of the Joint Director of Textiles (Sericulture), East Zone, Lake Town, Kolkata-89.	Rs.4,15,484/- (Rupees four lakh fifteen thousand four hundred eighty four)only.	Rs.10,390/- (Rupees ten thousand three hundred ninety)only.	-do-	-do-	-do-	-do-
3.	Roof treatment on G.C.I. sheet roof and wall Cabinet at 1st floor at Office campus of the Joint Director of Textiles (Sericulture), East Zone, Lake Town, Kolkata-89.	Rs.1,65,689/- (Rupees one lakh sixty five thousand six hundred eighty nine)only.	Rs.4,145/- (Rupees four thousand one hundred forty five)only.	-do-	-do-	-do-	-do-

Tender papers (NIT), Priced Schedule & Form-2911 (ii) etc. may be obtained/downloaded from seriwb.gov.org at free of cost. Tender should be submitted/dropped in the box kept at Head Quarters, Kolkata and papers should be arranged in the following manner.

Envelop - I, should be super scribed as Technical Bid for N.I.T No.....SL No. of Work, Name of agency and it should contain (Self Attested) PAN Card. Last I.T. Return, GSTIN Registration, P.T. Challan, Credential (similar nature of work at about 60% of Tender Value) EMD, and Sealed.


Envelop - II, should be super scribed as Financial Bid for N.I.T. No..... SL No. of Work. Name of Agency and should contain filled in - 2911 (ii) quoting the Rate and Sealed.

2(two) envelopes as noted above (I & II) should be put in a bigger envelop and sealed. Agency should write clearly N.I.T No., Name of Work, SL.No. and Name of Agency on this Envelope and drop the same as per schedule mentioned in this N.I.T.

Technical Bid will be opened first. Financial Bid will be opened only if the technical Bid is found acceptable.

Labour cess will be deducted from bill value as per Govt. Rules. All original copies are to be shown for verification. The details may be seen in the Office of the Commissioner of Textiles(Sericulture), West Bengal, 45, Ganesh Ch. Avenue (2nd floor),Kolkata-13 on any working days and Website : seriwb.gov.org. The Commissioner of Textiles(Sericulture), West Bengal reserves the right to reject/cancel all the applications without showing any reasons thereof. If any date as above happens to be holiday; the next working days will be considered as stipulated date. Acceptance of lowest tender is not obligatory.


N.S.C./K.V.P. will not be accepted as Earnest Money. Only the Bank Draft of a Nationalised Bank will be considered.


Executive Engineer,

Directorate of Textiles(Sericulture),West Bengal.

Priced Schedule for Renovation of existing reserviour and pipe line for Office and Staff Qtrs at the office campus of the Joint Director of Textiles (Sericulture), East Zone , Lake town under P.C.R. during 2016-17.

Sl.No.	Description of item	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
1.	<i>Labour for dismantling G.I. pipe with fittings.</i>				
	<i>(i). 40 mm</i>	247.00	m	8.00	1976.00
	<i>(ii). 20 mm</i>	122.00	m	6.00	732.00
	<i>(iii)., 50 mm</i>	13.00	m	8.00	104.00
2.	<i>Supplying, fitting and fixing PVC pipes for underground work of approved make (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted including cost of all materials ,jointing materials, cutting pipes, making threads ,cutting trenches upto 1.5 metre below surface in all sorts of soil and refilling the same as directed complete in all respect.</i>	200.00	m	327.00	65,400.00
	<i>(i).40 mm dia pipe</i>	85.00	m	150.00	12,750.00
3.	<i>Supplying, fitting and fixing PVC pipes of approved make of (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, making threads,fitting, fixing etc. complete in all respect including cost of all necessary fittings as required,jointing materials and two coats of painting with approved paint in any position above ground.</i>				
	<i>(i). 40 mm dia</i>	47.00	m	308.00	14,476.00
	<i>(ii). 20 mm dia</i>	37.00	m	136.00	5032.00
	<i>(iii).50 mm dia</i>	13.00	m	406.00	5278.00
4.	<i>Supplying, fitting and fixing gunmetal wheel valve of approved brand and make tested to 21 kg per sq. cm. (for water lines only). 40 mm dia.</i>	5	Each	2014.00	10,070.00
5.	<i>Chromium plated Stop Cock (Equivalent to Code No. 513(A) & 513(B) & Model - Tropical / Sumthing Special of ESSCO or similar</i>	28	Each	629.00	17,612.00
6.	<i>Polythene Bib Cock / Stop Cock (HD) with metal inlet (EMCO / ATLAS or equivalent)</i>	10	Each	100.00	1000.00
7.	<i>Supplying, fitting and fixing 10 litre P.V.C. low-down cistern conforming to I.S. specification with P.V.C. fittings</i>	10	Each	1181.00	11,810.00


 Executive Engineer,
 Directorate of Textiles (Sericulture),
 West Bengal

	complete, C.I. brackets including two coats of painting to bracket etc. direction of the EIC.				
8.	S.F & Fixing 3 Phase 2HP Centrifugal pump and base plate etc. complete.	1 set	Set	8146.00	8146.00
9.	S.F. & Fixing 32A TPN Main switch (Haval made with fuse.	1 no	Each	2402.00	2402.00
10.	S.F and Fixing 3 Phase Control Panel	1	Each	7690.00	7690.00
11.	Dismantling R.C. floor, roof, beams etc. including cutting rods and removing rubbish as directed within a lead of 75 m. including stacking of steel bars. (a) In ground	1.30	Cum	1975.00	2567.00
12	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor)	45.00	Sqm	360.00	16,200.00
13.	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction.	0.51	MT	61,936.00	31,587.00
14.	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor	6.50	Cum	7186.70	46,714.00
15.	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary With (1:4) cement mortar 10 mm thick.	60.00	Sqm	140.00	8400.00
16.	Neat cement punning about 1.5mm thick in wall, dado, window sill, floor etc.	60.00	Sqm	38.00	2280.00
17.	Supplying Fitting and fixing Manhole cover with rim 450mm x 100 mmdia.	2	Each	2364.00	4728.00
18.	Supplying Fitting and fixing Starter for Pump.	1	Each	1150.00	1150.00

TOTAL= Rs. 2,78,104.00

Rs . 2,78,104.00

(Rupees Two lakh seventy eight thousand one hundred four only).



Executive Engineer

Directorate of Textiles & Sericulture
West Bengal