

Government of Tender Notice

Invitation of Tender Notice Nos.19,20,21 & 22/Seri/Engg/Civil/PCR/MLD/2018-19.

Scaled Tenders are invited by the Executive Engineer, Directorate of Textiles (Sericulture), West Bengal, Ganesh Chandra Avenue(2nd floor), Kolkata - 13 for the following works in the district of Malda under P.C.R. works from the bonafide experienced and resourceful contractors having experience in such types of works in pure Govt. Department/Zilla Parishad.

NIT No.	Name of the Work	Estimated Cost	Earnest Money	Place of Work	Time of Completion
19	Construction of plinth protection of Rearing House with allied works and supplying, fitting & fixing of Grill at Office Building in position of damage concrete jali at Amrity Sericulture Nursery, Malda under P.C.R.	Rs.99,883.00 (Rupees ninety nine thousand eight hundred Eighty three) only.	Rs.2,500.00 (Rupees two thousand five hundred)only.	Amrity Sericulture Nursery, Amrity, Malda.	1(one) month from the date of issue of Work Order.
20	Repairing of Reeling Shed for Collapsible Gate window etc. with allied works at P.S.R.I., Malda under P.C.R.	Rs.99,971.00 (Rupees ninety nine thousand nine hundred seventy one) only.	Rs.2,500.00 (Rupees two thousand five hundred)only.	P.S.R.I., Malda.	-do-
21	Construction of Guard Wall at Kaliachak Cocoon Market, Malda under P.C.R. (Length : 7.00 mtr.)	Rs.99,921.00 (Rupees ninety nine thousand nine hundred twenty one)only	Rs.2,500.00 (Rupees two thousand five hundred)only	Kaliachak Cocoon Market, Malda.	-do-
22	Construction of Boundry wall (back side of Toilet) at Kaliachak Cocoon Market, Malda under P.C.R.	Rs.95,729.00 (Rupees ninety five thousand seven hundred twenty nine) only	Rs.2,400.00 (Rupees two thousand four hundred)only.	-do-	-do-


Tender papers (NIT, Priced Schedule & Form : 2911(ii) etc. may be obtained/down loaded from seriwb.gov.org at free of cost. Tender papers should be submitted in the box kept at Head Quarters, Kolkata & papers should be arranged in the following manner.

Last date and time of submission of Tender	04.09.2018 upto 3-00 P.M. at Head Quarters, Kolkata.
Date and time of opening of Tender	04.09.2018 upto 3-30 P.M. at Head Quarters, Kolkata.

Envelope-I, should be superscribed as Technical Bid for N.I.T. No.....of work. Name of the Agency and it should contain (Self attested) i) PAN Card. Last Income Tax Return. Valid GSTIN Registration, P.Tax, Challan. Credential (similar nature of work at about 60% of Tender value), E.M.D. and sealed.

Envelope-II, should be superscribed as Financial Bid for N.I.T. No.....of work, Name of Agency and should contain filed on 2911(ii) quoting the rate and sealed. 2(two) Nos. Envelopes as noted above (I&II) should be put in a bigger envelope and sealed. Agency should write clearly NIT No.....Name of Work, and Name of the Agency on this Envelope and drop the same as per schedule mentioned in this N.I.T.


The Technical Bid will be opened at first. The financial Bid will be opened only if the Technical Bid is found acceptable. Labour Cess will be deducted from Bill value as per Govt. Rules. All the original copies are to be shown for verification. The details may be seen in the Office of the **Commissioner of Textiles (Sericulture), Govt. of West Bengal, 45, Ganesh Chandra Avenue(2nd floor), Kolkata - 13** on any working days and in the Website : seriwb.gov.org. The Commissioner of Textiles (Sericulture), Govt. of West Bengal reserves the right to reject/accept all the applications without showing any reasons thereof. If any date as above happens to be holiday the next working day will be considered as stipulated date. Acceptance of lowest tender is not obligatory. N.S.C./K.V.P. will not be accepted as Earnest Money. Only the Bank Draft of a Nationalized Bank will be considered.


 Executive Engineer,
 Directorate of Textiles (Sericulture),
 West Bengal.

Bill of Materials Schedule for construction of Boundary wall (Back side of ex toilet) at Kaliachak cocoon market, Kaliachak, Malda under PCR(L-15.25m)

Sl. No.	PARTICULARS	QTY.	RATE	AMOUNT (Rs.)
1	Earth work in excavation of foundation trench or drain in all sorts of soil including removing spreading or stacking the spoils, within a lead of 75m.	5.70 m ³	119.27 / m ³	680.00
2	Single brick flat soling of picked jhama bricks including remming and dressing bed to proper level.	9.00 m ²	321.00 / m ²	2889.00
3	Cement concrete with (30 mm down graded) stone ballast excluding shuttering in (1:3:6) GF (a) 6:3:1 proportion.	1.00 m ³	4246.00 / m ³	4246.00
4	Ordinary cement concrete with graded stone chips 20 mm down nominal size excluding shuttering in G.F.(1:1.5:3) (i) In Ground floor Pakur variety.	2.70 m ³	5648.50 / m ³	15251.00
5	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc. including supply of rods, intial straightening and removal of loose rust (in necessary), Cutting to requisite length, hoking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every inter-section, complete as per drawing and direction. (i) Tor steel/Mild steel (ii) In ground floor.	0.27 MT	60205.00 / MT	16255.00
6	Hire and labour charges for shuttering with e=centering and necessary staging upto 4m.; using approved stout props and thick hard wood polanks of approved thickness with required bracing for concrete slabs, beams, after completion of works. (a) 25 mm to 30 mm thick wooden shuttering as per decision and direction of engineer-in charge. (i) Without staging (ii) With staging	2.50 m ² 22.00 m ²	205.00 / m ² 328.00 / m ²	513.00 7216.00
7	Earth work in filling in foundation trenches or plinth with good earth in layers not exceding 150 mm including watering and ramming etc. layer by layer complete. (iv) With earth obtained from excavation of foundation.	3.40 m ³	77.54 / m ³	264.00
8	Brick work with 1st class bricks in cement mortar (6:1) b) in superstructure in ground floor (i) in foundation.	0.80 m ³	5087.00 / m ³	4070.00
9	125 mm thick brick work with 1st class bricks in cement mortar (4:1) (i) In ground floor.	23.85 m ² 70.00 m ²	670.00 / m ² 159.00 / m ²	15980.00 11130.00
10	Plaster (to wall, floor ceiling etc.) with sand and cement mortar including off corners as directed with (6:1) cement mortar 20 mm thick (inside)	70.00 m ²	159.00 / m ²	11130.00
11	Neat cement punning about 1.5 mm thick in wall, dado, window, sills floor drain etc. in all floors about 1.5 mm thick.	14.00 m ²	34.00 / m ²	476.00
12	Protective and decorative acrylic exterior emulsion paint of approved quality after preparing the surface including scraping the same thoroughly (plastered or cement surface) as per manufacturer's specification. In ground floor iii) Two coats. In Ground floor.	56.00 m ²	101.00 / m ²	5656.00

Rs. ~~84626.76~~ 776.00
Add G.S.T. 12% Rs. ~~10155.00~~ 9573.00
Rs. ~~74781.83~~ 8349.00
Add labour cess @1% Rs. ~~74800.83~~ 893.00
Rs. ~~90242.00~~
95729.00


Executive Engineer
Directorate of Textiles (Sericulture)
West Bengal