

## Government Tender Notice

Invitation of Tender Notice No.24,25,26,27,28 & 29/Seri/Eng/Civil/PCR/MLD/2017-'18.

Sealed Tenders are invited by the **Executive Engineer, Directorate of Textiles(Sericulture), West Bengal**, 45, Ganesh Chandra Avenue,(2<sup>nd</sup> floor),Kolkata-13 for the following works at Sericulture Unit, in the district of Malda from the bonafide experienced and resourceful contractors having experienced in such type of works in pure Govt. Department/Office/Zilla Parishad.

Sl. No.	Name of the Work	Estimated Cost	Earnest money	Last date & time of Submission of Tender	Date of opening of Tender	Place of Work.	Time of Completion of work.
1.	Repairing of road with allied works of the Conference Room at P.S.R.I., Malda under P.C.R.	Rs.31,737/- (Rupees thirty one thousand seven hundred thirty seven) only.	Rs.800/- (Rupees eight hundred) only.	30.11.2017 upto 3-00 P.M. at H.Q.,Kolkata	30.11.2017 at 3-30 P.M. at H.Q. Kolkata.	P.S.R.I., Malda.	1(one) month from the date of issue of Work Order.
2.	Minor repairing of different Staff Qtrs., Main Gate of P.S.R.I. & different Staff Qtrs. incl. S & P works of the Deputy Director, Textiles(Sericulture), Malda under P.C.R.	Rs.99,135.00/- (Rupees ninety nine thousand one hundred thirty five)only.	Rs.2,480/- (Rupees two thousand four hundred eighty)only.	-do-	-do-	Office Campus of the Deputy Director of Textiles(Sericulture), Malda.	-do-
3.	Repairing of Rearing House at Krishnapur Seri. Nursery, Malda under P.C.R.	Rs.4,99,964/- (Rupees four lakh ninety nine thousand nine hundred sixty four) only.	Rs.12,510/- (Rupees twelve thousand five hundred ten Only.	-do-	-do-	Krishnapur Seri. Graft Nursery, Malda.	-do-
4.	Repairing of Rearing House at Amrity Sericulture Nursery, Amrity, Malda under P.C.R..	Rs.4,99,705/- (Rupees four lakh ninety nine thousand seven hundred five) only.	Rs.12,500/- (Rupees twelve thousand five hundred only.	-do-	-do-	Amrity Sericulture Nursery, Malda.	-do-
5.	Construction of Toilet Urinal sets incl. plumbing works for Buyers & Sellers' at Kaliachak Cocoon Market, Malda under P.C.R.	Rs.4,93,896/- (Rupees four lakh ninety three thousand eight hundred ninety six) only.	Rs.12,350/- (Rupees twelve thousand three hundred fifty)only.	-do-	-do-	Kaliachak Cocoon Market Complex, Malda.	-do-

Construction of Toilet (Gents' & Ladies') incl. plumbing works at Sadullapur Sericulture Nursery, Malda.	Rs.4,28,566/- (Rupees four lakh twenty eight thousand five hundred sixty six ) only.	Rs.10,715/- (Rupees ten thousand seven hundred fifteen)only.	-do-	-do-	Sadullapur Sericulture Nursery, Malda.	-do-
--	--	--	------	------	--	------

Tender papers (NIT), Priced Schedule & Form-2911 (ii) etc. may be obtained/downloaded from [seriwb.gov.org](http://seriwb.gov.org) at free of cost.

Tender should be submitted/dropped in the box kept at Head Quarters, Kolkata and papers should be arranged in the following manner.


**Envelop - I**, should be super scribed as Technical Bid for N.I.T No.....SL No. of Work, Name of agency and it should contain (Self Attested ) PAN Card. Last I.T. Return, GSTIN Registration, P.T. Challan. Credential (similar nature of work at about 60% of Tender Value) EMD etc. and sealed.

**Envelop - II**, should be super scribed as Financial Bid for N.I.T. No..... SL No. of Work, Name of Agency and should contain filled in Form - 2911 (ii) quoting the Rate and Sealed.

2(two) envelopes as noted above (I & II) should be put in a bigger envelop and sealed. Agency should write clearly N.I.T. No., Name of Work, SL.No. and Name of Agency on this Envelope and drop the same as per schedule mentioned in this N.I.T.

Technical Bid will be opened first. Financial Bid will be opened only if the technical Bid is found acceptable. Labour cess will be deducted from bill value as per Govt. Rules. All original copies are to be shown for verification. The details may be seen in the Office of the **Commissioner of Textiles(Sericulture), West Bengal**, 45, Ganesh Ch. Avenue (2nd floor),Kolkata-13 on any working days and **WEB SITE : [seriwb.gov.org](http://seriwb.gov.org)**. **The Commissioner of Textiles(Sericulture), West Bengal** reserves the right to reject/cancel all the applications without showing any reasons thereof. If any date as above happens to be holidays the next working days will be considered as stipulated date. Acceptance of lowest tender is not obligatory.

N.S.C./K.V.P. will not be accepted as Earnest Money. Only the Bank Draft of a Nationalised Bank will be considered.



**Executive Engineer,  
Directorate of Textiles (Sericulture),  
West Bengal.**

**Price Schedule for Construction of Toilet (Gents and ladies) including plumbing works at Sadullapur  
Graft Nrusery Sadullapur, Malda under PCR.**

SI No.	P A R T I C U L A R S	QTY.	RATE	AMOUNT. Rs.
01.	Earth work in excavation of foundation trench or Drain in all sorts of soil including removing spreading or stacking the spoils, within a lead of 75m.	6m <sup>3</sup>	120.47/m <sup>3</sup>	723.00
02.	Single brick flat soling of picked jhama bricks including remming and dressing bed to proper level.	30m <sup>2</sup>	338.00/m <sup>2</sup>	10140.00
03.	Cement concrete with (30 mm down graded ) stone ballast shuttering in (1:3:6) GF(a)6:3:1 proportion.	3m <sup>3</sup>	4831.00/m <sup>3</sup>	14493.00
04.	Ordinary Cement concrete with graded stone chips 20 mm down nominal size excluding shuttering in G.F (1:1;5:3)(i) In Ground floor. Pakur variety.	7m <sup>3</sup>	6442.80/m <sup>3</sup>	45100.00
05.	Hire and labour charges for shuttering with e=centering and necessary staging upto 4m. ;using approved stout props and thick hard wood polanks of approved thickness with required bracing for concrete slabs, beams, after completion of works. (a) 25 mm to 30 mm thick wooden shuttering as per decision and direction of Engineer-in-charge. (i) with out staging. (ii) With staging.	10m <sup>2</sup> 62m <sup>2</sup>	221.00/m <sup>2</sup> 351.00/m <sup>2</sup>	2210.00 21762.00
06.	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc. including supply of rods, intial straightening and removal of loose rust (in necessary), Cutting to requisite length, hoking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every inter-section, complete as per drawing and direction. (i) Tor steel/Mild steel (i) In ground floor.	7.00 Qtl.	6304.90/Qtl.	44134.00
07.	Brick work with 1 <sup>st</sup> class bricks in cement mortar (6:1) b) in superstructure In ground floor (i) In Foundation. (ii)In superstructure G.F.	2.20m <sup>3</sup> 0.30m <sup>3</sup>	5253.00/m <sup>3</sup> 5478.00/m <sup>3</sup>	11557.00 1643.00
08.	125 mm thick brick work with 1 <sup>st</sup> class bricks in cement mortar (4:1) (i) In Ground floor.	40m <sup>2</sup>	726.00/m <sup>2</sup>	29040.00
09.	M.S. or W.I.Ornamental grill of approved design joints continuously welded with M.S., W.I.Flats and bars of windows, railing etc. fitted and fixed with necessary screws and lugs. In ground floor.	0.80Qtl	8381.00/Qtl.	6705.00
10.	Earth work in filling in foundation trenches or plinth with good earth in layerfs not exccding 150 mm including watering and ramming etc. layer by layer complete. (vii) With earth obtained from excavation of foundation.	2.90m <sup>3</sup>	78.31/m <sup>3</sup>	227.00

Contd.....(p).....(2).....

(2)

11.	With carried earth arranged by the contractor within a radius of 3Km including earth of carried earth.	3m <sup>3</sup>	358.96/m <sup>3</sup>	1077.00
12.	Plaster (to wall, floor ceiling etc.) with sand and cement mortar including rounding off corners as directed.(i) With (1:4) cement mortar 10 mm thick. (i) 6:1 cement mortar 20 mm thick(inside) (ii) G.F. 1:6 cement mortar 15 mm thick.	10m <sup>2</sup> 65m <sup>2</sup> 52m <sup>2</sup>	136.00/m <sup>2</sup> 173.00/m <sup>2</sup> 150.00/m <sup>2</sup>	1360.00 11245.00 7800.00
13.	Neat cement punning about 1.5 mm thick in wall, dado, window, sills, floor drain etc. in all floors about 1.5 mm thick.	8m <sup>2</sup>	39.00/m <sup>2</sup>	312.00
14.	White washing including cleaning and smoothening surface thoroughly (All floors) (Three coats) ( on new works only)	46m <sup>2</sup>	20.81/m <sup>2</sup>	957.00
15.	Acrylic exterior grade Acrylic acrylic primer ( as per manufacturer's specification) including cleaning and smoothening of surface.(a) In Ground Floor.	44m <sup>2</sup>	34.04/m <sup>2</sup>	1498.00
16.	Protective and decorative acrylic exterior emulsion paint of approved quality after preparing the surface including scraping the same thoroughly (plastered or cement surface) as per manufacturer's specification. In ground floor iii) Two coats. In Ground floor.	44m <sup>2</sup>	108.00/m <sup>2</sup>	4752.00
17.	Painting with best quality synthetic enamel paint (i) On steel or other metal surface.	4.40m <sup>2</sup>	86.00/m <sup>2</sup>	378.00
18.	S/F 1 <sup>st</sup> quality ceramic tiles in walls and floor to match with the existing (i) Floor. (ii) Wall.	10m <sup>2</sup> 29.50m <sup>2</sup>	834.00/sqm 844.00/sqm	8340.00 24898.00
19.	Orissa pattern water closet in white glazed vitreous china ware of approved make in passion. 530mm x 410mm	2 Nos.	1907.00/nos	3814.00
20.	Cast Iron'S' trap conforming to IS 3989/1970 including lead	2 Nos.	923.00/Nos	1846.00
21.	S/F/F approved patern vent cowl I.C.I. conforming to I.S.S. and painting 2 coats.	2 Nos.	427.00/Nos.	854.00
22.	Construction of Inspection Pit of inside measurement 600 mm x 600mm x upto 600mm deep with 250mm th. 1 <sup>st</sup> class brick work in CM 1:6 all sides (page-81/sl. No.1)	3 Nos.	7322.00/Nos.	21966.00
23.	Construction of septic tank as per approved drawing with 1 <sup>st</sup> class brick work in cement mortar (1:4) as per direction 20 user .	1 No.	49664.00/each	49664.00
24.	Construction of circular soak wall 2.50m deep with dry brick work upto 1.60 m from the bottom as per direction.	1 No.	16677.00/each.	16677.00

Contd.....(P).....(3).....

25.	S/F/F peets valve full way gun metal standered pattern best quality of approved brand with fitting.	2 Nos.	807.00/Nos.	1614.00
26.	Supplying PVC water storage tank of approved quality with closed top with lid black multilayer. 1000 litre capacity.	1 No.	6110.00/each.	6110.00
27.	Labour for hoisting plastic water storage tank upto 1500 litre capacity.	1No.	97.00/each.	97.00
28.	Labour for punching hole in plastic water storage tank up to 50 mm dia.	4 Nos.	19.00/each.	76.00
29.	Chromium plated stop cock.	4 Nos.	855.00/Nos.	3420.00
30.	Supplying, fitting and fixing of chromium plated bib cock code No. 511 model tropical approved make and brand tested to 21 Kg. per sq. cm.	6 Nos.	843.00/Nos.	5058.00
31.	Towel Rails with 2 brackets C.P cover brush 25 mm dia 450 mm long.	2 Nos.	494.00/Nos.	988.00
32.	Bevel edged mirror 5.5 thick silver red with brush cp hinges.	2 Nos.	467.00/Nos.	934.00
33.	10 lit porcelain low down cistern of approved make with out fitting and brackets.	2 Nos.	2567.00/each.	5134.00
34.	White vitereous china best quality approved make wash basin with CL brackets.	1 No.	2504.00/Nos.	2504.00
35.	PVC pipe of approved made and conforming to ASMB 20 dia	20m	136.00/m	2720.00
36.	Flat back urinal in white vitreous china made of approved make in passion.	1 Nos.	820.00/Nos.	820.00
37.	S/F/F squanting plate with integral flushing in white vitreous china ware of approved make 450 mm x 350 mm.	1No.	1103.00/each.	1103.00
38.	S/F/F in position G.I. pipes of TATA make for under grand works with all necessary accessories (i) 25 mm dia.	60m	368.00/m	22080.00
39.	Supplying fitting and fixing Factory make per laminated P.V.C. door frame of size 50mm x 47 mm with a wall thickness of 5 mm, made out of extruded 5mm pre laminated P.V.C. sheet miter cut at two corners and joined eith two nos. of 1.5 mm long brackets of 15 mm x 15 mm M.S.square tube etc. complete as per Manufacturer's specification and direction of Engineer-in-charge.	15m	586.00/m	8790.00

40.	Supplying fitting and fixing 30 mm thick both side prelaminated factory made solid panel P.V.C. door shutter consisting of outer frame made out of M.S.tubes of 19 guage thickness and size 19 mm x 19 mm for styles, top and bottom rails, M.S. frame shall have cost of steel primers of approved make and manufacturer. M.S. frame covered with 5 mm th. Heat moulded PVC'C' channel of size 30 mm th. 70mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on either sides forming styles and 5 mm th. 95 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm tapered in 45 degree on the inner side to form top & bottom rail and 115 mm wide etc. complete as per direction of Engineer-in-charge.	5.04m <sup>2</sup>	2277.00/m <sup>2</sup>	11476.00
41.	S/F cast Iron soil pipe with bobbins, nail etc. including making holes.	10m	795.00/m	7950.00
42.	Removal of rubbish earth etc. from the working site.	15m <sup>3</sup>	168.00/Cum	2520.00

Total Rs. 4,28,566.00

*ey 10/8/17*  
Executive Engineer  
Directorate of Textiles (Sericulture)  
West Bengal.