

Government Tender Notice

Invitation of Tender Notice No. Seri/3,4,5/PCR(ELEC)/Alipurduar/17-18.(2nd Call)

Sealed Tenders are invited by the Executive Engineer, Sericulture, West Bengal, 45, Ganesh Chandra Avenue, (2nd floor), Kolkata-13 for the following Electrical works at Kumargram Eri Nursery, Alipurduar from the bonafide experienced and resourceful Electrical contractors having experienced in such type of works in pure Govt. Department/Office/Zilla Parishad.

Sl. No	Name of work	Estimated Cost (Rs.)	Earnest Money (Rs.)	Last dt. & Time of submission of Tender	Date of opening of Tender	Place of Work	Time of Completion
1.	Electrical wiring for the 2 nos Qrts & Restraining ACSR, painting of Pole, Compound light etc at Kumargram Eri Nursery, Alipurduar.	136785.00	3420.00	29.06.17 upto 3.00 pm. At H.Q.	29.06.17 After 3.30 pm.	Kumargram Eri Nursery, Alipurduar.r	1 month from the issue dt. Of work order
2.	Electrification works for the Office-Cum Grainage building (2 storaid)at Kumargram Eri Nursery, Alipurduar.	274293.00	6857.00	29.06.17 upto 3.00 pm. At H.Q.	29.06.17 After 3.30 pm.	Kumargram Eri Nursery, Alipurduar.	1 month from the issue dt. Of work order
3.	Electrification works for the Rearing House & Grainage bldg at Kumargram Eri Nursery, Alipurduar.	361900.00	9048.00	29.06.17 upto 3.00 pm. At H.Q.	29.06.17 After 3.30 pm.	Kumargram Eri Nursery, Alipurduar.	1 month from the issue dt. Of work order

Tender papers (N.I.T), Priced Scheduled & Form - 2911(ii) etc. may be obtained down loaded from **WEB SITE : seriwbgov.org.** at free of cost.

Tender should submitted/dropped in the Box kept at Head Quarters Kolkata and papers should be arranged in the following manner:

Envelop - I, should be super scribed as Technical Bid for N.I.T No.Sl. No. of work, Name of Agency and it should contain (Self Attested) i) PAN Card, Last I.T. Return, VAT Regn., P.T. Challan. Credential (similar nature of work at about 60% of Tender Value), EMD, Electrical & Supervisory License & Sealed.

Envelop - II, should be super scribed as Financial Bid for N.I.T. No.....Sl. No. of work, Name of Agency and should contain : Filled in **Form : 2911(ii)** quoting the Rate and Sealed.

Two envelopes as noted above (I & II) should be put in a bigger envelop and sealed. Agency should write clearly N.I.T. No..... Name of Work, Sl.N **WEB SITE : seriwbgov.org.** and name of Agency on this Envelop and drop the same as per schedule mentioned in this N.I.T.

Technical Bid will be opened first. Financial Bid will be opened only if the Technical Bid is found acceptable. Labour cess will be deducted from Bill Value as per Govt. Rule. All the original copies are to be shown for verification. The details may be seen in the Office of the Commissioner of Textiles & Sericulture, Govt. of West Bengal, 45, Ganesh Chandra Avenue (2nd floor), Kolkata - 13 on any working day and in **WEB SITE : seriwbgov.org.** The Commissioner of Textiles (Sericulture), West Bengal reserves the right to reject/cancel all the applications without showing any reasons thereof. If any date as above happens to be holiday the next working days will be considered as stipulated date. Acceptance of lowest tender is not obligatory. N.S.C., K.V.P. will not be accepted as Earnest Money. Only the Bank Draft of a Nationalised Bank will be considered.


Executive Engineer,
Directorate of Textiles (Sericulture)
West Bengal.

09/06/17

Priced Schedule for the Electrical wiring for the 2 nos Qrts & Restraining ACSR, painting of Pole, Compound light etc at Kumargram Eri Nursery, Alipurduar.

- | | | | |
|------------|--|--|--------------|
| 1. | S/F Outdoor type New generation energy saving & environmental friendly long life Varsatile pressure die cast aluminium IP65 roadway luminaire with high power LED as light surce (Cat no- LHEWDRP7PN1W025) HAVELLS make with Lamp type 25W LED 5000K, HAVELLS make. | | |
| 4nos. | @ Rs.4351.00 each | | Rs. 17404.00 |
| 2. | S/Erection of Galv. Stay set complete with 7/10 SWG G.I standard stay wire (45 ton capacity) 1.8mts X 16mm dia Galv stay rod 100X100X6mm thick Galv M.S anchor plate 356mmX13mm Galv bow (with ratchet type nut) thimble Galv box type stay clamp in CC foundtion (6:3:1) having hard jhama metal incl providing earth connection. | | |
| 4 Nos. | @ Rs.1486.00 per mt. | | Rs. 5944.00 |
| 3. | S/Erection of Galv "D" iron clamp complete with suitable pole clamp 75mmX88mm porcelain shackle insulator & 15mm dia Galv bolts & nuts including painting. | | |
| 14 nos. | @ Rs.137.00 per set | | Rs. 1918.00 |
| 4. | S/Erection of 75mmX88mm porcelain shackle insulator complete with 190X30X5mm Galv (hot dip) strips with 15.88mm dia Galv nuts & bolts etc for conductor. | | |
| 14 nos. | @ Rs.77.00 each | | Rs. 1078.00 |
| 5. | Supply & Erection of 6 SWG G.I (hot dip) continuous Earth wire with Galv. Earth clamp. | | |
| 90 mts.. | @ Rs.18.20 per mt. | | Rs. 1638.00 |
| 6. | Re-straining the existing ACSR conductor including S/F binding wire with 9 SWG soft Al. wires. | | |
| 450mts. | @ Rs.7.00 per mt. | | Rs. 3150.00 |
| 7. | Painting of steel Tubular pole up to 9mt. length and 2 coats synthetic enamel paints over one coat red led/ zinc chromate incl, preparation of surface by sand paper/emery paper, cleaning for receiving fresh coat of paint. | | |
| 4 no poles | @ Rs.506.00 per pole | | Rs. 2024.00 |
| 8. | S/F PVC safety device for up to 6 conductor's incl earth wire vertical disposition. | | |
| 16 sets | @ Rs.125.00 per set | | Rs. 2000.00 |
| 9. | S/Laying 2 core 6sq.mm PVC/A cable partly in the under ground trench as per PWD schedule & partly embedded in wall as per PWD schedule for Street lught 4 | | |
| 50 mts. | @ Rs. 192.24 per mt. | | Rs. 9612.00 |
| 10. | S/F 240V, 32A SPN mains switch HAVELLS make for Pump Room. | | |
| 1no | @Rs.4173.00 each | | Rs. 4173.00 |
| 11. | Distribution Wiring in 1.1 KV grade 2X22/0.3 (1.5 sq.mm) single core standard "FR" PVC insulated & unsheathed single core standard copper wire (Approved make) in suitable size PVC casing-capping (Precision make) with 1.1 KV grade 1X22/0.3 (1.5 sq.mm) for ECC incl necy. Fittings to light/fan/call bell point with piano-key-type switch (Anchor make) fixing on sheet steel fabricated switchboard with Perspex top cover incl earthing attachment as to G.S. (5mt. average long) | | |
| 30 points | @Rs. 612.25 per point | | Rs. 18368.00 |
| 12. | S/F 250V 5Amp piano-key-type plug socket with switch (Anchor) without top in existing switch board incl. connection & as per P.W.D schedule. | | |
| 8 points | @ Rs.70.00 per point | | Rs 560.00 |
| 13. | Earthing the whole installation by 2inch. dia 10ft.long G.I pipe (ISI midium) and as per PWD schedule. | | |

M

	2 sets	@Rs.1500.00 per set	Rs. 3000.00
14.	S/F 250v AC/DC superior type call bell (Anchor 8320) on TW board incl S/F TW board.		
	2nos.	@ Rs.127.00 each	Rs. 254.00
15.	Wiring in 1.1 KV grade 2X36/0.3 (2.5sq. mm) single core standard "FR" PVC insulated & unsheathed single core standard copper wire (Approved make) with 1.1 KV grade 1X36/0.3 (2.5 sq. mm) single core standard "FR" PVC insulated & unsheathed single core standard copper wire (Approved make) in 20mm size rigid conduit 'FR' (Precision) incl necessary fitting for main line & 15A plug point.		
	80 mts.	@ Rs. 136.00 per mt.	Rs. 10880.00
16.	S/F 250V, 15A flush type plug socket with 15A Piano-key type switch (Anchor) on sheet metal box with bakelite top cover and earthing attachment incl. sheet metal box with bakelite top cover as per PWD schedule.		
	2nos.	@ Rs.326.25 each	Rs. 653.00
17.	S/F 2+6 Single Door MCB DBs with BusBar, Neutral Limk, and Earth Bar fitted with 1 no 32A DP Isolator, Havells make & 6nos 6A SP MCB & Havells make on iron angle frame on wall incl connection.		
	2 sets	@ Rs.2975.00 each	Rs 5950.00
18.	Dismetalling the existing damage electrical works for the Qrts, Godown ect. as per instruction of EIC.		
	1 job.	@ Rs.1000.00 per job	Rs. 1000.00
19.	S/F 9" dia Exhaust fan Crompton Greaves make single-phase incl. connection as required incl. shutter & louver and making hole on wall and mending good damages to wall & as per PWD schedule.		
	4sets	@ Rs.2287.00 per set	Rs. 9148.00
20.	S/F 240V, 32A SPN mains witch (Havells make)		
	2nos.	@ Rs.1425.00 each	Rs. 2850.00
21.	S/F socket type fan regulator (Step type) & as per instruction of EIC		
	4 nos.	@ Rs.254.00 each	Rs. 1016.00
22.	S/Laying 2 core 4sq.mm PVC/A cable partly in the under ground trench as per PWD schedule & partly embedded in wall as per PWD schedule from main panel to 2nos pump.		
	65mts.	@ Rs. 189.00 per mt.	Rs. 12285.00
23.	S/F 32mm dia protection pipe as per PWD Schedule.		
	6mts	@ Rs.354.00 per mt.	Rs. 2124.00
24.	Wiring in 1.1 KV grade 2X56/0.3 (4sq. mm) single core standard "FR" PVC insulated & unsheathed single core standard copper wire (Approved make) with 1.1 KV grade 1X36/0.3 (2.5 sq. mm) single core standard "FR" PVC insulated & unsheathed single core standard copper wire (Approved make) as ECC in suitable size PVC casing-capping (Precision) incl necessary from meter to main switch .		
	35mts.	@Rs. 171.00 per mt.	Rs. 5985.00
25.	S/F Bulk head light fittings of (Bajaj make) suitable for 100 Watt lamp complete with glass, wire-guard & holder.		
	4 set	@ Rs.334.00 per set	Rs. 1336.00

Rs.124350.00

M

3


BF..... Rs, 124350.00

Add Dist. Charge @10%

(+)

Rs. 12435.00

Rs. 136785.00


Executive Engineer
Directorate of Textiles (Seri)
West Bengal