

## Government Tender Notice

### Invitation of Tender Notice No. Seri/3,4,5/PCR(ELEC)/Alipurduar/17-18.( 2<sup>nd</sup> Call )

Sealed Tenders are invited by the Executive Engineer, Sericulture, West Bengal, 45, Ganesh Chandra Avenue,(2<sup>nd</sup> floor),Kolkata-13 for the following Electrical works at Kumargram Eri Nursery, Alipurduar from the bonafide experienced and resourceful Electrical contractors having experienced in such type of works in pure Govt. Department/Office/Zilla Parishad.

Sl. No	Name of work	Estimated Cost (Rs.)	Earnest Money (Rs.)	Last dt. & Time of submission of Tender	Date of opening of Tender	Place of Work	Time of Completion
1.	Electrical wiring for the 2 nos Qrts & Restraining ACSR, painting of Pole, Compound light etc at Kumargram Eri Nursery, Alipurduar.	136785.00	3420.00	29.06.17 upto 3.00 pm. At H.Q.	29.06.17 After 3.30 pm.	Kumargram Eri Nursery, Alipurduar.r	1 month from the issue dt. Of work order
2.	Electrification works for the Office-Cum Grainage building (2 storaid)at Kumargram Eri Nursery, Alipurduar.	274293.00	6857.00	29.06.17 upto 3.00 pm. At H.Q.	29.06.17 After 3.30 pm.	Kumargram Eri Nursery, Alipurduar.	1 month from the issue dt. Of work order
3.	Electrification works for the Rearing House & Grainage bldg at Kumargram Eri Nursery, Alipurduar.	361900.00	9048.00	29.06.17 upto 3.00 pm. At H.Q.	29.06.17 After 3.30 pm.	Kumargram Eri Nursery, Alipurduar.	1 month from the issue dt. Of work order

Tender papers ( N.I.T), Priced Scheduled & Form - **2911(ii)** etc. may be obtained down loaded from **WEB SITE : [seriwb.gov.org](http://seriwb.gov.org)**. at free of cost.

Tender should submitted/dropped in the Box kept at Head Quarters Kolkata and papers should be arranged in the following manner:

**Envelop - I**, should be super scribed as Technical Bid for N.I.T No. ....Sl. No. of work, Name of Agency and it should contain (Self Attested) i) PAN Card, Last I.T. Return, VAT Regn., P.T. Challan. Credential (similar nature of work at about 60% of Tender Value ), EMD, Electrical & Supervisory License & Sealed.

**Envelop - II**, should be super scribed as Financial Bid for N.I.T. No.....Sl. No. of work, Name of Agency and should contain : Filled in **Form : 2911(ii)** quoting the Rate and Sealed.

Two envelopes as noted above (I & II) should be put in a bigger envelop and sealed. Agency should write clearly N.I.T. No..... Name of Work, Sl.N **WEB SITE : [seriwb.gov.org](http://seriwb.gov.org)**. and name of Agency on this Envelop and drop the same as per schedule mentioned in this N.I.T.

Technical Bid will be opened first. Financial Bid will be opened only if the Technical Bid is found acceptable. Labour cess will be deducted from Bill Value as per Govt. Rule. All the original copies are to be shown for verification. The details may be seen in the Office of the Commissioner of Textiles & Sericulture, Govt. of West Bengal, 45, Ganesh Chandra Avenue (2nd floor), Kolkata - 13 on any working day and in **WEB SITE : [seriwb.gov.org](http://seriwb.gov.org)**. The Commissioner of Textiles (Sericulture), West Bengal reserves the right to reject/cancel all the applications without showing any reasons thereof. If any date as above happens to be holiday the next working days will be considered as stipulated date. Acceptance of lowest tender is not obligatory. N.S.C., K.V.P. will not be accepted as Earnest Money. Only the Bank Draft of a Nationalised Bank will be considered.

  
Executive Engineer,  
Directorate of Textiles (Sericulture)  
West Bengal.

09/06/17

**Priced Schedule for the Electrification works for the Office-Cum Grainage building (2 storaid)at  
Kumargram Eri Nursery, Alipurduar.**

=====		
1. Earthing the whole installation by 2inch. dia 10ft.long G.I pipe (ISI midium) and as per PWD schedule.		
2sets	@Rs.1500.00 per set	Rs. 3000.00
2. Distribution Wiring in 1.1 KV grade 2X22/0.3 (1.5 sq.mm) single core standard "FR" PVC insulated & unsheathed copper wire (Approved make) in 20mm PVC rigid conduit FR(Precision make) with 1.1 KV grade 1X22/0.3 (1.5 sq.mm) for ECC incl necy. Fittings to light/fan/call bell point with piano-key-type switch fixing on MS SRC sheet steel (16SWG) switch board cum JB on wall complete w3ith 2nos suitable size PH & N copper bar with Perspex top cover 3mm thick incl 175mmX100mmX65mm inspection box making earthing attachment as to G.S. (6mt. average long)		
54 points	@Rs.791.00 per point	Rs. 42714.00
3. S/F 250V 5Amp piano-key-type plug socket with switch (Anchor) without top in existing switch board incl. connection & as per P.W.D schedule.		
8 points	@ Rs.70.00 per point	Rs 560.00
4. Wiring in 1.1 KV grade 2X36/0.3 (2.5sq. mm) single core standard "FR" PVC insulated & unsheathed copper wire (Approved make) with 1.1 KV grade 1X36/0.3 (2.5 sq. mm) single core standard "FR" PVC insulated & unsheathed copper wire (Approved make) in 20mm size rigid conduit 'FR' (Precision) incl necessary fitting for main line & outdoor light.		
130mts	@Rs. 136.00 per mt.	Rs. 17680.00
5. S/F SP&N enclosure with 2 poies & earth Metal Plug & Socket inciuding 20A SPN MCB (Havells make (CAT no.DHDPUSN020) for power plug.		
4nos	@ Rs.1175.00 each	Rs. 4700.00
6. Wiring in 1.1 KV grade 2X56/0.3 (4sq. mm) single core standard "FR" PVC insulated & unsheathed copper wire (Approved make) with 1.1 KV grade 1X36/0.3 (2.5 sq. mm) single core standard "FR" PVC insulated & unsheathed copper wire (Approved make) as ECC in suitable size PVC casing-capping (Precision) incl necessary fitting for power plug & AC point.		
130 mts.	@Rs. 171.00 per mt.	Rs. 22230.00
8. S/F socket type fan regulator (Step type) & as per instruction of EIC.		
12 nos.	@ Rs.254.00 each	Rs. 3048.00
9. S/F 32mm dia protection pipe as per PWD Schedule.		
6 mts	@ Rs.253.00 per mt.	Rs. 1518.00
10. S/F MIROLTA Slim batten 36W Hf with suitable for single TMSS20/136 lamp with reflector.		
18 Nos.	@ Rs.699.00 per set	Rs. 12582.00
11. S/F 6 way double Door Horizontal TPN MCB distribution board CRABTREE make (Cat No-DCDKTHODCW06) with 1no 63Amps FP Isolator, 8nos 6A MCB & 10nos 15A SP MCB CRABTREE make on iron angle frame on wall.		
1sets.	@ Rs.7576.00 per set	Rs. 7576.00
12. S/Laying 4 core 16sq.mm PVC/A cable partly in the underground trench 460mm wide X 760mm average depth ,with brick protection on the top of the cable with 8 nos bricks per metre ,incl filling the space between the bricks & cable and also the trench with sifted soil leveing up & restoring surface duly rammed & partly embedded in wall as per PWD schedule from O.H line to main switch of Grainage Room (Ground floor).		
20mts.	@ Rs. 464.41 per mt.	Rs. 9288.00

M

S/Laying 3½ core 35sq.mm PVC/A cable partly in the underground trench 460mm wide X 760mm average depth, with brick protection on the top of the cable with 8 nos bricks per metre, incl filling the space between the bricks & cable and also the trench with sifted soil leveling up & restoring surface duly rammed & partly embedded in wall as per PWD schedule from O.H line to main switch of OH to Main panel & main panel to OH line

80mts.	@ Rs. 464.41 per mt.	Rs. 37153.00
13. S/F 415V, 63A TPN mains switch HAVELLS make (Cat no- IHSRTE4063) for RH-2.		
1no	@Rs.4173.00 each	Rs. 4173.00
14. S/F CFL lamp 20Wt Philips make		
16nos	@Rs.240.00 each	Rs. 3840.00
15. S/F 12" dia Exhaust fan Crompton Greaves make(EXHD300-4-1) single-phase incl. connection as required incl. shutter & louver and making hole on wall and mending good damages to wall & as per PWD schedule.		
4 sets	@ Rs.3725.00 per set	Rs. 14900.00
16. S&F sheet metal inspection box (150mm X 100mm X 65mm) flushed in wall by housing the same after cutting wall etc including earthing attachment, painting & good damages to wall.		
4nos.	@ Rs.144.00 each	Rs. 576.00
18. S/F 1 poles 15 Amps MCB with sheet steel enclosure of Havells make (Cat no-DHDESSP)		
1 no.	@ Rs.394.68 each	Rs. 395.00
19. S/F Outdoor type New generation energy saving & environmental friendly long life Varsatile pressure die-cast aluminium IP65 roadway luminaire with high power LED as light surge (Cat no- LHEWDRP7PN1W025) HAVELLS make with Lamp type 25W LED 5000K, HAVELLS make.		
4 nos.	@ Rs.4351.00 each	Rs. 17404.00
21. S/Laying 2 core 4sq.mm PVC/A cable partly in the underground trench as per PWD schedule & partly embedded in wall as per PWD schedule for Street light & main panel to 1 <sup>st</sup> floor.		
60 mts.	@ Rs. 299.00 per mt.	Rs. 17940.00
22. S/F 9" dia Exhaust fan Crompton Greaves make single-phase incl. connection as required incl. shutter & louver and making hole on wall and mending good damages to wall & as per PWD schedule.		
1set	@ Rs.2287.00 per set	Rs. 2287.00
22. Supply & Fixing floor/wall mounted pedestal type M.S angle iron frame (size of angle iron 40X40X6mm & M.S. flat of size 40X6mm comprising of the following accessories to main switch by 7/20 PVC copper wire incl. socketing and painting.		
a) S/F 415V, 160A TPN mains witch (Havells make) .....		1 No
b) S/F 500V, 200A sheet metal iron clad Bus-bar chamber (size 500mmX 150mmX1mt long) with 4(four) nos Al.Bars (3X25mmX5mm) on angle iron frame on wall .....		1No
c) S/F 415V, 160A TPN mains witch (Havells make) .....		1 No
d) S/F 415V, 63A TPN mains witch (Havells make) .....		1 No
e) S/F 240V, 32A SPN mains witch (Havells make) .....		3 Nos
f) S/F danger board, Indicator lamp (3nos) R Y B .....		1set
1 set	@Rs. 25793.00 per set	Rs. 25793.00
		-----
		Rs 249357.00

M

BF.....Page no-2


Rs. 249357.00

Add Dist. Charge @10.00%

(+)

Rs. 24936.00

Rs. 274293.00

  
Executive Engineer  
Directorate of Textiles (Seri)  
West Bengal