

Government Tender Notice.

Tender Notice No.Seri/Eng./Civil/54 & 55/RKVY/MID(W)/2017-'18

Sealed Tenders are invited by the Executive Engineer, Sericulture, West Bengal, 45, Ganesh Chandra Avenue (2nd floor), Kolkata-13 for the following works at Debra Sericulture Complex in Midnapore (West) from the bonafide experienced and resourceful contractors having experienced in such type of works in pure Govt. Department/Office/Z.P. P

NIT No.	Name of the Work.	Estimated Cost.	Earnest Money	Time of completion of Work.	Place of Work.
54	Internal Path-way in front of Grainage Building at Debra Sericulture Complex, Paschim-Medinipur under R.K.V.Y. works.	Rs.2,00,982/- (Rupees Two Lakh Nine Hundred Eighty Two) only.	Rs.5,025/- (Rupees Five Thousand Twenty Five) only.	1(one) month	Debra Sericulture Complex, Debra, Paschim-Medinipur.
55	Construction of Chain-link fencing at Debra Sericulture Complex. Paschim-Medinipur under R.K.V.Y. works. (<i>allied works</i>)	Rs. 71,400/- (Rupees Seventy One Thousand Four Hundred) only.	Rs.1,790/- (Rupees One Thousand Seven Hundred Ninety) only.	1(one) month	Debra, Paschim-Medinipur.

Tender Papers (NIT, Priced Schedule & Form 2911(ii) etc.) may be obtained/downloaded from Website : seriwb.gov.org at free of cost.

Tender should be submitted/dropped in the Box kept at Head Quarters, Kolkata and papers should be arranged in the following manner.

Last date and time of submission of Tender.	04.01.2018 upto 3:00 pm ^{upto 3:00 pm} at Headquarter, Kolkata.
Date of time of opening of Tender	04.01.2018 upto 3:00 pm ^{upto 3:30 pm} at Headquarter, Kolkata.

Envelope - I, should be super scribed as Technical Bid for N.I.T.No....., Sl.No. of work. Name of the Agency that it should contain Self Attested PAN Card. Last I.T. Return, GST IN Registration, P.T. Challan, Credential (Similar nature of work at about 60% of Tender value), E.M.D and sealed.

Envelope - II, should be super scribed as Financial Bid for N.I.T. No....., Sl.No. of work, Name of Agency and should contain filed on 2911 (ii) quoting in Rate and Sealed.

2(two) Envelopes as noted above (I & II) should be put in a bigger Envelope and sealed. Agency should write clearly N.I.T. No..... Name of Work, SL. No. and Name of Agency on this Envelope and drop the same as per scheduled mentioned in this N.I.T.

The Technical Bid will be opened first. The Financial Bid will be opened only if the Technical Bid is found acceptable.

Labour Cess will be deducted from Bill value as per Govt. Rules. All original copies are to be shown for verification. The details may be seen in the Office of the Commissioner of Textiles (Sericulture), West Bengal 45, Ganesh Ch. Avenue (2nd floor) , Kolkata - 13 on any working days and in website : seriwb.gov.org. The Commissioner of Textiles (Sericulture), West Bengal reserves the right to reject/accept all the applications without showing any reasons thereof. If any date as above happens to be holiday the next working day will be considered as stipulated date.

N.S.C./K.V.P. will not be accepted as Earnest Money. Only the bank Draft of a Nationalized Bank will be considered as earnest money.

Acceptance of lowest Tender is not obligatory.

Notwithstanding anything contained in this Notice Inviting Tender, the other terms and conditions and special terms and conditions will remain binding upon all concerned

[Signature]
Executive Engineer,
Directorate of Textiles(Sericulture),
West Bengal,
Dated 21/12 2017.

Memo.No. 1174(3) ENG/Civil/RKVY/MID(W)/1(Vol.-I),

Copy forwarded for information & necessary action to :-


1. The Deputy Director of Textiles (Sericulture), Midnapore(West).
2. The Notice Board of this Directorate, Headquarters, Kolkata.
3. The Website of this Directorate of Textiles (Sericulture), West Bengal.

[Signature]
Executive Engineer,
Directorate of Textiles(Sericulture),
West Bengal.

Priced Schedule for the for construction of Internal path way in front of Grainage building at
Debra Sericulture Farm, Debra, West Midnapur District.

Sl	Description of item	Qty	Unit	Rate	Amount
1	Earth work in filling in compound, tank, low land, ditches etc. with good earth, in layers not exceeding 150 mm. including breaking clods and consolidating the same by ramming and dressing complete. With earth obtained by fresh excavation upto 1800 mm. depth (including the cost of excavation from land arranged by the Deptt. within a lead of 100 m.)	30.00	Cum	120.47	3,614.10
2	125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor.	8.10	Sqm	759.00	6,147.90
3	Single Brick Flat Soling of picked jhama Bricks including ramming and dressing bed to proper level and filling joints with local sand.	115.00	Sqm	362.00	41,630.00
4	Filling in foundation or plinth by silver sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (Payment to be made on measurement of finished quantity	16.00	Cum	533.06	8,528.96
5	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor)	20.00	Sqm	97.00	1,940.00
6	Reinforcement for reinforced concrete working all sorts of structures including distribution bars, stirrups, binders etc. initial straightening and removal of loose rust (if necessary), Cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every	255.00	kg	61.78	15,753.90
7	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. (i) Pakur Variety	17.5	Cum	7049.56	1,23,367.30
				Rs.	2,00,982.16

(Rupees Two Lakh nine hundred eighty two) only


 Executive Engineer
 Directorate of Textiles (Sericulture)
 Government of West Bengal