

Government Tender Notice

Invitation of Tender Notice No.65 & 66/Seri/Eng/Civil/PCR/DARJ(P)/2019-20.

Sealed Tenders are invited by the Executive Engineer, Sericulture, West Bengal, 45, Ganesh Chandra Avenue, (2nd floor), Kolkata-13 for the following works at Matigara Sericulture Complex, and S.D.F., Naxalbari, Darjeeling under P.C.R. from the bonafide experienced and resourceful contractors having experienced in such type of works in pure Govt. Department/Zilla Parishad.

Sl	Name of the Work	Estimated Cost	Earnest Money	Place of Work.	Time of completion
1.	Construction of Drain North-Eastern corner at Matigara Sericulture Complex, Darjeeling under P.C.R.	Rs.78,641/- (Rupees Seventy Eight thousand Six hundred Forty One) only.	Rs.1,970/- (Rupees One thousand Nine hundred Seventy) only.	Matigara Sericulture Complex, Darjeeling.	One month from the date of issue of Work Order.
2.	Repairing of Step for 2-storied Rearing House & construction of Culvert in front of wooden Rearing House at SDF, Naxalbari, Darjeeling.	Rs.71,668/- (Rupees Seventy One thousand Six hundred Sixty Eight) only	Rs.1,795/- (Rupees One Thousand Seven hundred Ninety Five) only.	S.D.F., Naxalbari, Darjeeling.	-do-

Tender papers (NIT), Priced Schedule & Form-2911(ii) etc. may be obtained/downloaded from seriwb.gov.org at free of cost.

Tender should be submitted/dropped in the box kept at Head Quarters, Kolkata and papers should be arranged in the following manner.


Last date & time of submission of Tender	19-08.2019 upto 3-00 P.M. at Head Quarters, Kolkata.
Date & time of opening of Tender	19.08.2019 upto 3-30 P.M. at Head Quarters, Kolkata.

Envelope - I, should be superscribed as Technical Bid for N.I.T No.....SL No. of Work, Name of agency and it should contain (Self Attested) PAN Card, Last I.T. Return, valid GSTIN Registration, Profession Tax Challan, Credential (similar nature of work at about 60% of Tender Value) EMD etc. and sealed.

Envelope - II, should be super scribed as Financial Bid for N.I.T. No..... SL No. of Work, Name of Agency and should contain filled in - 2911 (ii) quoting the Rate and Sealed.

2(two) envelopes as noted above (I & II) should be put in a bigger envelop and sealed. Agency should write clearly N.I.T. No., Name of Work, SL.No. and Name of Agency on this Envelope and drop the same as per schedule mentioned in this N.I.T. Technical Bid will be opened first. Financial Bid will be opened only if the technical Bid is found acceptable. Labour cess will be deducted from bill value as per Govt. Rules. All original copies are to be shown for verification. The details may be seen in the Office of the Commissioner of Textiles(Sericulture), West Bengal, 45, Ganesh Ch, Avenue (2nd floor),Kolkata-13 on any working days and web site seriwb.gov.org. The Commissioner of Textiles(Sericulture), West Bengal reserves the right to reject/cancel all the applications without showing any reasons thereof. If any date as above happens to be holidays the next working days will be considered as stipulated date. Acceptance of lowest tender is not obligatory.

N.S.C./K.V.P. will not be accepted as Earnest Money. Only the Bank Draft of a Nationalised Bank will be considered as Earnest money. Acceptance of lowest Tender is not obligatory. Notwithstanding anytime contained in this Notice Inviting Tender, the other terms & conditions and special terms & conditions will remain binding upon all concerned.



Executive Engineer,
Directorate of Sericulture,
West Bengal.

Dated, 9.8.2019.

453C3)
Memo.No. /ENG/CIVIL/PCR/Darj(P)/1(Vol.-5),

Copy forwarded for information & necessary action to :-

1. The Joint Director of Sericulture, North Zone, Siliguri, Darjeeling.
2. The Notice Board of this Directorate, Headquarters, Kolkata.
- ✓ 3. The Website of this Directorate of Sericulture, West Bengal.


Executive Engineer,
Directorate of Sericulture,
West Bengal.

Priced schedule for construction of drain at north east corner of Matigara Sericulture complex, Matigara, Darjeeling under PCR.

Sl.	Description of item	Quantity	Unit	Rate (Rs.)	Amount (Rs.)
1.	Dismantling all types of plain cement concrete works, stacking serviceable materials at site and removing rubbish as directed within a lead of 75.	2.32	Cu.m	1417.00	3287.00
2.	Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete. (a) Depth of excavation not exceeding 1,500 mm.	1.50	Cum	119.27	179.00
3.	Bailing out water from the campus of o/o the J.D.S., North Zone, Matigara.	1305.00	Cum	20.88	27,248.00
4.	Brick work with 1st class bricks in cement mortar (4:1) In foundation and plinth.	2.00	Cum	6719.00	13,438.00
5.	Single Brick Flat Soling of picked jhama Bricks including ramming and dressing bed to proper level and filling joins with local sand.	4.00	Sqm	323.00	1292.00
6.	Hire and labour charges for shuttering with cantering and necessary staging up to 4 m. using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams, columns, lintels curved or straight including fitting, fixing and striking out after completion of works. (up to roof of ground floor) 25 mm. to 30 mm. thick wooden shuttering as per decision & direction of Engineer-in-charge.	15.00	Sqm.	209.00	3135.00
7.	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc. initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. For works in foundation, basement and upto roof of ground floor / upto 4m. Tor steel/Mild steel Other than TATA/NTNL/SAIL	90.00	K.G.	71.26	6413.00
8.	Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. (i) Pakur Variety.	1.50	Cum	5254.00	7881.00

9.	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course scaffolding/staging where necessary (ground floor). [Excluding cost of chipping over concrete surface] With 1:4 cement mortar ,15 mm. thick plasters.	30.00	Sqm	155.00	4650.00
10.	Neat cement punning about 1.5 mm. thick in wall, dado, window, sills, floor, drain etc	20.00	Sqm	31.00	620.00
11.	Labour Charges for taking out chain-link fencing from the existing wall and refitting the same.	12.00	Sqm	70.00	840.00

TOTAL=Rs.68, 983.00

Add 12% GST=Rs. 8,278.00

Add Labour welfare cess @ 1%=Rs. 690.00

Total= Rs.78,641.00

(Signature)
Executive Engineer
Directorate of Textiles (Sericulture)
Government of West Bengal