

# GOVERNMENT TENDER NOTICE

**Notice Inviting Tender Nos.83,84,85 & 86/SERI/PCR/UD/2017-'18.**

Sealed quotations are invited by the Executive Engineer, Directorate of Textiles(Sericulture), West Bengal, 45, Ganesh Chandra Avenue (2nd floor), Kolkata-13 for Constructional works in Uttar Dinajpur district from the enlisted contractors of P.W. Deptt. (Elec.), CB Directorate, as well as from the bonafide experienced and resourceful outside contractors having experience in such type of works in Govt. Department / Zilla Parishad.

NIT No.	Name of the Work.	Estimated Cost	Earnest Money	Place of Work.	Time of completion of work.
83	Repairing of 5-HP Sub-merssible Pump Motor set at Sohurai Sericulture Composite Unit, Raigunj, Uttar Dinajpur under P.C.R.	Rs.42,354/- (Rupees forty two thousand three hundred fifty four) only.	Rs.1,060/- (Rupees one thousand sixty) only.	Sohurai Sericulture Composite Unit, Raigunj, Uttar Dinajpur.	1(one) month from the date of issue of Work Order.
84	Renovation of Office Building at Sohurai Sericulture Composite Unit, Raigunj, Uttar Dinajpur under P.C.R.	Rs.4,99,862/- (Rupees four lakh ninety nine thousand eight hundred sixty two) only.	Rs.12,500/- (Rupees twelve thousand five hundred) only.	-do-	-do-
85	Repairing of Boundry wall (behind Reeling House No.1 & Reeling House No.2 at at Sohurai Sericulture Composite Unit, Raigunj, Uttar Dinajpur (Flood damaged 130 mtr.) under P.C.R.	Rs.4,99,318/- Rupees four lakh ninety nine thousand three hundred eighteen) only.	Rs.12,485/- (Rupees twelve thousand four hundred eighty five) only.	-do-	-do-
86	Repairing of Boundry wall (behind Office Building & front side of the Farm) at Sohurai Sericulture Composite Unit, Raigunj, Uttar Dinajpur (Flood damaged 120 mt.) under P.C.R. works.	Rs.4,99,221/- (Rupees four lakh ninety nine thousand two hundred twenty one)only	Rs.12,485/- (Rupees twelve thousand four hundred eighty five) only.	-do-	-do-

The quotation Papers (N.I.T., Schedule of Works, & Form : 2911(i/ii) etc.) may be obtained/downloaded from [seriwb.gov.org](http://seriwb.gov.org) at free of cost. Duly filled quotation to be submitted/dropped in the Box kept at Head Quarters, Kolkata and papers should be arranged in the following manner.

**Envelope - I**, should be superscribed as Technical Bid for N.I.T. No....., Sl.No. .... of Work. Name of the Agency and it should contain copy of Self Attested i) PAN Card. (ii) Last I.T. Return. (AY 2016-17) (iii) GST IN Registration Certificate which is valid for the current period, (iv) Professional Tax Clearance and Challan for the last financial year, (v) Credential for Similar nature of work at about 60% of Tender value) and E.M.D. Sealed.

**Envelope - II**, should be super scribed as Financial Bid for N.I.T.No....., Sl.No. of Work. Name of Agency and should contain filed on 2911 (ii) quoting in Rate both in figure and words, and Sealed.

2(two) Envelopes as noted above (I & II) should be put in a bigger Envelope and sealed. Agency should write clearly N.I.T. No..... Name of Work, SL. No. and Name of Agency on this Envelope and drop the same as per scheduled mentioned in this N.I.T.


Last date and time of submission of Tender	19-03-2018 at 3-00 P.M. at Headquarters, Kolkata.
Date of opening of Tender	19.03.2018 after 3-30 P.M. at Headquarters, Kolkata.

Technical Bid will be opened first. Financial Bid will be opened only if the Technical Bid is found acceptable.

Labour Cess will be deducted from Bill value as per Govt. Rules. All original copies are to be shown for verification. The details may be seen in the Office of the Commissioner of Textiles (Sericulture), West Bengal 45, Ganesh Ch. Avenue (2nd floor), Kolkata - 700 013 on any working days and in website : [seriwb.gov.org](http://seriwb.gov.org).

N.S.C./K.V.P. will not be accepted as Earnest Money. Only the Demand Draft / Bankers Cheque of a Nationalized Bank will be considered.

The Commissioner of Textiles (Sericulture), West Bengal reserves the right to reject/accept all the applications without showing any reasons thereof. If any date as above happens to be holiday the next working day will be considered as stipulated date. Acceptance of lowest Tender is not obligatory. Notwithstanding anything contained in this N.I.T., the general and other terms and conditions will be binding upon all concerned.

  
Executive Engineer,

Directorate of Textiles(Sericulture),  
West Bengal.

Memo.No. 4055 (B) ENG/CIVIL/PCR/UD/1 (Vol.-4),

Dated, 22/02/2018.

Copy forwarded for information & necessary action to :-

1. The Assistant Director of Textiles (Sericulture),  
Karnajora, Raigunj, Uttar Dinajpur.
2. The Notice Board of this Directorate, Headquarters, Kolkata.
3. The Website of this Directorate of Textiles (Sericulture), West Bengal.

*ey 22/2/18*  
Executive Engineer,  
Directorate of Textiles (Sericulture),  
West Bengal.

Price Schedule for repairing of Office building at Raiganj Seri. Comp. Unit, Saharai, Raiganj, Uttar Dinajpur, under PCR.

01.	Dismantling RC floor beams etc including cutting rods and removing rubbish as directed.	3m <sup>3</sup>	1956.00/m <sup>3</sup>	5868.00
02.	Dismantling all types of plain cement concrete works. Stacking as directed. Within a lead of 75 m.	20.20m <sup>3</sup>	939.00/m <sup>3</sup>	18968.00
03.	Stripping off worn out plaster and racking out joints of wall ceiling etc. up to any height, and in any floor including removing rubbish as directed. Within a lead of 75 m.	661m <sup>2</sup>	19.00/m <sup>2</sup>	12559.00
04.	Ordinary cement concrete (Mix 1:2:4) with graded stone chips (20 mm (20mm dia) excluding shuttering and reinforcement if any pakur variety. (i) In G.F.	3m <sup>3</sup>	5750.10/m <sup>3</sup>	17250.00
05.	Hire and labour charges for shuttering with centering and necessary staging up to 4 m and thick hard wood planks of approved thickness with required bracing for concrete slab, beams etc. including fitting and fixing and striking out after completion of works.(I) In G.F.	68m <sup>2</sup>	328.00/m <sup>2</sup>	22304.00
06.	Reinforcement for reinforced concrete work in all sorts of structure including distribution bars, strups, binder etc. and removal of loose rust ( if necessary) cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection complete as per drawing as directed. Tor Steel. (i) In G.F.	2.00 Qtl..	6020.50/Qtl	12041.00
07.	Ordinary cement concrete M-15 (mix 1:1.5:3) with graded stone chips (20 mm dia) excluding shuttering and reinforcement if any Pakur Variety.	15.20m <sup>3</sup>	6364.10/m <sup>3</sup>	96734.00
08.	Labour for taking out doors and windows including shutter for repair and replacement of different parts of the frame and re fixing the same including mending good all damage complete.	31 m <sup>2</sup>	119.00/m <sup>2</sup>	3689.00
09.	Dismantling artificial stone flooring up to 50 mm thick by carefully chiselling with out damaging the base and removing rubbish as directed. Within a lead of 75 m. In G.F.	21m <sup>2</sup>	50.00/m <sup>2</sup>	1050.00
10.	Wood work in doors and windows frame fitted and fixed complete including a protection coat of painting at the contact surface of the frame excluding cost of concrete Hard wood.neem.	0.45m <sup>3</sup>	50963.00/m <sup>3</sup>	22933.00
11.	Taking out grills from wooden frame including cutting lugs and re fixing the same.	5 Nos.	99.00/each	495.00
12.	S/F/F M.S. clamp for fitting doors and windows frame made of flat ;bent bar and bifurcated with necessary screws etc. by cement concrete (1:2:4) as per direction.40mmx 6mmx250mm length.	46 Nos.	29.00/each	1334.00

Contd...(P).....(2).....

22/2/18  
 Executive Engineer,  
 Directorate of Textiles (Sericulture),  
 West Bengal

13.	Artificial stone floor, dado, stair case etc. with cement concrete (4:2:1) with stone chips laid in panels as directed with toppings made with ordinary cement including smooth finishing all complete including all materials and labour 3mm thick topping 35 mm thick chap.	21m <sup>2</sup>	319.00/m <sup>2</sup>	6699.00
14.	MS structural works in columns, beams etc with simple rolled structural members, angle, chanel etc. connected to one another as per design complete including welding fabrication hoisting and erection all complete for lader.	75 Kg.	60.23/Kg	4517.00
15.	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed And racking out joints or roughening of surface including threading, nosing and drip course where necessary. (A) In G.F.: Z(iv) With (4:1) cement mortar, 15mm thickness (v) With (6:1) cement mortar (inside), 20 mm thickness. (vi) With (6:1) cement mortar (outside), 15mm thickness.	136m <sup>2</sup> 273m <sup>2</sup> 252m <sup>2</sup>	157.00/m <sup>2</sup> 162.00/m <sup>2</sup> 141.00/m <sup>2</sup>	21352.00 44226.00 35532.00
16.	Neat cement punning about 1.5 mm thick in wall, dado window sills, floor, drain etc.	78m <sup>2</sup>	34.00/m <sup>2</sup>	2652.00
17.	M.S.or W.I ornamental grill of approved design joints continuously welded with M.S., W.I. Flats and bars of windows, railing etc. Fitted and Fixed with necessary screws and lugs. Grill weighing above 10 Kg/M <sup>2</sup> up to 16 Kg./m <sup>2</sup>	185 Kg.	73.71/Kg.	13636.00
18.	Panel shutter of doors and windows as per design including fitting and fixing the same in position but excluding the cost of hinges. 35mm thick shutter with 19 mm thick panel. Gamar.	5.63m <sup>2</sup>	2789.00/m <sup>2</sup>	15702.00
19.	Shutter 2/3 <sup>rd</sup> panel and 1/3 <sup>rd</sup> glazed of doors and windows as per design and with ordinary glass fitted with putty bed and teak wood beads and nails including fitting and fixing shutter in position. 35mm thick shutter, 19 mm thick panel. Gamar.	8.64m <sup>2</sup>	3046.00/m <sup>2</sup>	26317.00
20.	Styles and rails of wooden (Payment to be made on area of new work only) 35 mm thick shutter Gamar.	0.80m <sup>2</sup>	2178.00/m <sup>2</sup>	1742.00
21.	Iron butt hinges of approved quality fitted and fixed with steel screws with ISI mark.(i) 75mm x 47mmx1.70mm. (ii)100mm x 58mm x 1.90mm	40 Nos. 18 Nos.	31.00/each 47.00/each	1240.00 846.00
22.	Iron socket bolt of approved quality fitted and fixed complete. 100mm long x 10 mm dia bolt.	20 Nos.	40.00/each	800.00
23.	Iron skeleton bolt of approved quality fitted and fixed complete. 375 mm long x 10 mm dia. Rod.	3 Nos.	92.00/each	276.00
24.	Iron hasp bolt of approved quality fitted and fixed completes with 16 mm dia rod with center bolt and round fitting 300mm long.	3 Nos.	166.00/each	498.00
25.	Iron catch hook of approved quality fitted and fixed to shuttering and chowkat 6mm dia x 100 mm long.	12 Nos.	36.00/each	432.00
26.	Anodized aluminium D-type handle of approved quality, fitted & fixed complete 100 mm grip x 10 mm dia.	16 Nos.	69.00/each	1104.00
27.	White washing including cleaning and smoothening surface thoroughly – 2 coats.	520m <sup>2</sup>	18.14/m <sup>2</sup>	9433.00

Contd.....(P)....(3).....

22/2/18  
Executive Engineer,  
Directorate of Textiles (Sericulture),  
West Bengal

--(3)--

28.	Applying exterior grade acrylic primer of approved quality and brand on plastered surface incl. Preparing the surface one coat. Water based interior grade.	208m <sup>2</sup>	30.80/m <sup>2</sup>	6406.00
29.	Protective and decorative Acrylic exterior emulsion paint of approved quality as per manufactured specification and as per direction of the E.I.C.	208m <sup>2</sup>	101.00/m <sup>2</sup>	21008.00
30.	Priming one coat on plastered or timber surface including smoothening surface by sand of papering etc.	38m <sup>2</sup>	38.00/m <sup>2</sup>	1444.00
31.	Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface.-2 coats if necessary.(i) On timber wood (ii) On steel	80m <sup>2</sup> 60m <sup>2</sup>	81.00/m <sup>2</sup> 72.00/m <sup>2</sup>	6480.00 4320.00

Rs. 4,41,887.00

Add G.S.T. 12 % (+) Rs. 53,026.00

Rs. 4,94,913.00

Add Labour welfare cess @ 1% (+) Rs. 4,949.00

**Total Rs. 4,99,862.00**

*22/1/18*

Executive Engineer,  
Directorate of Textiles ( Sericulture )  
West Bengal.