

GOVERNMENT TENDER NOTICE

Notice Inviting Tender Nos.83,84,85 & 86/SERI/PCR/UD/2017-'18.

Sealed quotations are invited by the Executive Engineer, Directorate of Textiles(Sericulture), West Bengal, 45, Ganesh Chandra Avenue (2nd floor), Kolkata-13 for Constructional works in Uttar Dinajpur district from the enlisted contractors of P.W. Deptt. (Elec.), CB Directorate, as well as from the bonafide experienced and resourceful outside contractors having experience in such type of works in Govt. Department / Zilla Parishad.

NIT No.	Name of the Work.	Estimated Cost	Earnest Money	Place of Work.	Time of completion of work.
83	Repairing of 5-HP Sub-merssible Pump Motor set at Sohurai Sericulture Composite Unit, Raigunj, Uttar Dinajpur under P.C.R.	Rs.42,354/- (Rupees forty two thousand three hundred fifty four)only.	Rs.1,060/- (Rupees one thousand sixty) only.	Sohurai Sericulture Composite Unit, Raigunj, Uttar Dinajpur.	1(one) month from the date of issue of Work Order.
84	Renovation of Office Building at Sohurai Sericulture Composite Unit, Raigunj, Uttar Dinajpur under P.C.R.	Rs.4,99,862/- (Rupees four lakh ninety nine thousand eight hundred sixty two) only.	Rs.12,500/- (Rupees twelve thousand five hundred) only.	-do-	-do-
85	Repairing of Boundry wall (behind Reeling House No.1 & Reeling House No.2 at at Sohurai Sericulture Composite Unit, Raigunj, Uttar Dinajpur (Flood damaged 130 mtr.) under P.C.R.	Rs.4,99,318/- Rupees four lakh ninety nine thousand three hundred eighteen) only.	Rs.12,485/- (Rupees twelve thousand four hundred eighty five) only.	-do-	-do-
86	Repairing of Boundry wall (behind Office Building & front side of the Farm) at Sohurai Sericulture Composite Unit, Raigunj, Uttar Dinajpur (Flood damaged 120 mt.) under P.C.R. works.	Rs.4,99,221/- (Rupees four lakh ninety nine thousand two hundred twenty one)only	Rs.12,485/- (Rupees twelve thousand four hundred eighty five) only.	-do-	-do-

The quotation Papers (N.I.T., Schedule of Works. & Form : 2911(i/ii) etc.) may be obtained/downloaded from seriwb.gov.org at free of cost. Duly filled quotation to be submitted/dropped in the Box kept at Head Quarters, Kolkata and papers should be arranged in the following manner.

Envelope - I, should be superscribed as Technical Bid for N.I.T. No..... Sl.No. of Work. Name of the Agency and it should contain copy of Self Attested i) PAN Card. (ii) Last I.T. Return. (AY 2016-17) (iii) GST IN Registration Certificate which is valid for the current period, (iv) Professional Tax Clearance and Challan for the last financial year, (v) Credential for Similar nature of work at about 60% of Tender value) and E.M.D. Sealed.

Envelope - II, should be super scribed as Financial Bid for N.I.T.No....., Sl.No. of Work, Name of Agency and should contain filed on 2911 (ii) quoting in Rate both in figure and words, and Sealed.

2(two) Envelopes as noted above (I & II) should be put in a bigger Envelope and sealed. Agency should write clearly N.I.T. No.,... Name of Work, SL. No. and Name of Agency on this Envelope and drop the same as per scheduled mentioned in this N.I.T.


Last date and time of submission of Tender	19-03-2018 at 3-00 P.M. at Headquarters, Kolkata.
Date of opening of Tender	19.03.2018 after 3-30 P.M. at Headquarters, Kolkata.

Technical Bid will be opened first. Financial Bid will be opened only if the Technical Bid is found acceptable.

Labour Cess will be deducted from Bill value as per Govt. Rules. All original copies are to be shown for verification. The details may be seen in the Office of the Commissioner of Textiles (Sericulture), West Bengal 45, Ganesh Ch. Avenue (2nd floor), Kolkata - 700 013 on any working days and in website : seriwb.gov.org.

N.S.C./K.V.P. will not be accepted as Earnest Money. Only the Demand Draft / Bankers Cheque of a Nationalized Bank will be considered.

The Commissioner of Textiles (Sericulture), West Bengal reserves the right to reject/accept all the applications without showing any reasons thereof. If any date as above happens to be holiday the next working day will be considered as stipulated date. Acceptance of lowest Tender is not obligatory. Notwithstanding anything contained in this N.I.T., the general and other terms and conditions will be binding upon all concerned.


Executive Engineer,
Directorate of Textiles(Sericulture),
West Bengal.

Memo.No. 4055(8) ENG/CIVIL/PCR/UD/1 (Vol.-4),

Dated, 22/02/2018.

Copy forwarded for information & necessary action to :-

1. The Assistant Director of Textiles (Sericulture),
Karnajora, Raigunj, Uttar Dinajpur.
2. The Notice Board of this Directorate, Headquarters, Kolkata.
3. The Website of this Directorate of Textiles (Sericulture), West Bengal.

ey 22/2/18
Executive Engineer,
Directorate of Textiles (Sericulture),
West Bengal.

Price Schedule for repairing of boundary wall (behind of office building and front side of the farm) at Sericulture comp. Unit, Soharai Raiganj in the Dist. Of Uttar Dinajpur (Damage by flood in 2017) L – 120M.

01.	Dismantling RC floor beams etc including cutting rods and removing rubbish as directed.	2.50m ³	1956.00/m ³	4890.00
02.	Dismantling all types of masonry excepting cement concrete stacking serviceable materials at site and removing rubbish as directed.	6.00 m ³	447.00/m ³	2682.00
03.	Brick work with 1 st class bricks in cement mortar (6:1) i) In foundation ii) In superstructure.	6.00m ³ 6.50m ³	4901.00/m ³ 5124.00/m ³	29406.00 33306.00
04.	Ordinary cement concrete M-15 (mix 1:1.5:3) with graded stone chips (20 mm dia) excluding shuttering and reinforcement Pakur variety.	6.10m ³	6364.10/m ³	38821.00
05.	Reinforcement for reinforced concrete work in all sorts of structure including distribution bars, strups, binder etc. and removal of loose rust (if necessary) cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection complete as per drawing as directed. Tor Steel. (i) In G.F.	0.574MT	60205.00/MT	34558.00
06.	Hire and labour charges for shuttering with centering and necessary staging up to 4 m and thick hard wood planks of approved thickness with required bracing for concrete slab, beams etc. including fitting and fixing and striking out after completion of works.(I) In G.F without staging. (ii) With staging.	25m ² 43m ²	205.00/m ² 328.00/m ²	5125.00 14104.00
07.	125 mm thick brick work with 1 st class bricks in cement mortar (1:4) in G.F.	181m ²	674.00/m ²	121994.00
08.	Earth work in filling in foundation trenches or plinth with food earth in layers not exceeding 150 mm including working and ramming etc. Layer by layer complete. With carried earth arranged by the contractor with in a radius of 3Km including cost of carried earth.	79.20m ³	379.82/m ³	30082.00
09.	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and racking out joints or roughening of surface including throating, nosing and drip course where necessary. (i) With (4:1) cement mortar, 20 mm thick.	518m ²	181.00/m ²	93758.00
10.	Neat cement punning about 1.5 mm thick in wall, dado, window sills, floor, drain etc.	64m ²	34.00/m ²	2176.00

Contd....(2).....

22/2/18
Executive Engineer,
Directorate of Textiles (Sericulture),
West Bengal

----(2)-----

11.	Protective and decorative Acrylic exterior emulsion paint of approved quality as per manufacturer specifications and as per direction of the E.I.C. (Normal)	454m ²	67.00/m ²	30418.00
-----	--	-------------------	----------------------	----------

441320.00

Add G.S.T. 12 % (+) 52958 .00

Rs.494278.00

Add Labour welfare cess @ 1% (+) 4943 .00

Total Rs.499221.00



**Executive Engineer,
Directorate of Textiles (Sericulture)
West Bengal.**