

Government Tender Notice

Invitation of Tender Notice Nos.13 & 14/Seri/Eng/Civil/RKVY/MLD/2017-'18.

Sealed Tenders are invited by the Executive Engineer, Sericulture, West Bengal, 45, Ganesh Chandra Avenue (2nd floor), Kolkata-13 for the following works at Kaliachak Cocoon Market Complex, Malda under **R.K.V.Y.** from the bonafide experienced and resourceful contractors having experienced in such type of works in pure Govt. Department/ Zilla Parishad.

Sl. No.	Name of the Work.	Estimated Cost.	Earnest Money	Last date and time of submission of Tender.	Date and time of opening of Tender	Place of Work.	Time of completion of Work.
1.	Renovation of existing Godown-cum-TSC Office-II for installation of Cocoon Drier at campus of Kaliachak Cocoon Market Complex, Malda under R.K.V.Y. works.	Rs.4,96,667/- (Rupees four lakh ninety six thousand six hundred sixty seven) only.	Rs.12,420/- (Rupees twelve thousand four hundred twenty) only	10.10.2017 upto 3-00 P.M. at H.Q., Kolkata.	10-10-2017 at 3-30 P.M. at H.Q., Kolkata.	Kaliachak Cocoon Market Complex, Malda.	2(two) months from the date of issue of Work Order.
2.	Construction of Meter Room attach with Watchman's Room of Cocoon Drier at campus of Kalichak Cocoon Market Complex, Malda under R.K.V.Y. works.	Rs.2,36,780/- (Rupees two lakh thirty six thousand seven hundred eighty) only.	Rs.5,920/- (Rupees five thousand nine hundred twenty) only	-do-	-do-	-do-	1(one) month from the date of issue of Work Order.

Tender Papers (NIT, Priced Schedule & Form : 2911(ii) etc.) may be obtained/downloaded from seriwb.gov.org at free of cost.


Tender should be submitted/dropped in the Box kept at Head Quarters, Kolkata and papers should be arranged in the following manner.

Envelope - I, should be super scribed as Technical Bid for N.I.T.No..... Sl.No. of work. Name of the Agency that it should contain (Self Attested) i) PAN Card. Last I.T. Return, **GST IN** Registration, P.T. Challan. Credential (Similar nature of work at about **60%** of Tender value), E.M.D, Electrical & Supervisory License and sealed.

Envelope - II, should be super scribed as Financial Bid for N.I.T. No..... Sl.No. of work, Name of Agency and should contain filed on **2911 (ii)** quoting in Rate and Sealed.

2(two) Envelopes as noted above (**I & II**) should be put in a bigger Envelope and sealed. Agency should write clearly N.I.T. No..... Name of Work, SL. No. and Name of Agency on this Envelope and drop the same as per scheduled mentioned in this N.I.T.

Technical Bid will be opened first. Financial Bid will be opened only if the Technical Bid is found acceptable. Labour Cess will be deducted from Bill value as per Govt. Rules. All original copies are to be shown for verification. The details may be seen in the Office of the **Commissioner of Textiles (Sericulture), West Bengal, 45, Ganesh Ch. Avenue (2nd floor) , Kolkata - 13** on any working days and in website : seriwb.gov.org. The Commissioner of Textiles (Sericulture), West Bengal reserves the right to reject/accept all the applications without showing any reasons thereof. If any date as above happens to be holiday the next working day will be considered as stipulated date. Acceptance of lowest Tender is not obligatory. N.S.C./K.V.P. will not be accepted as Earnest Money. Only the bank Draft of a Nationalized Bank will be considered.


Executive Engineer,
Directorate of Textiles(Sericulture),
West Bengal

Price Schedule for construction of Meter room attach with watch man's room for cocoon Drier at the campus of Kalaichak cocoon market, Kaliachak in the Dist. Of Malda under R.K.V.Y.

SI No.	PARTICULARS	QTY.	RATE	AMOUNT. Rs.
01.	Earth work in excavation of foundation trench or Drain in all sorts of soil including removing spreading or stacking the spoils, within a lead of 75m.	5m ³	120.47/m ³	602.00
02.	Single brick flat soling of picked jhama bricks including remming and dressing bed to proper level.	26m ²	338.00/m ²	8788.00
03.	Cement concrete with (30 mm down graded) stone ballast shuttering in (1:3:6) GF(a)6:3:1 proportion.	2.60m ³	4831.00/m ³	12561.00
04.	Ordinary cement concrete with with graded graded stone chips 20 mm nominal size excluding shuttering in G.F (1:1;5:3)(i) In Ground floor Pakur variety.	7m ³	6576.50/m ³	46036.00
05.	Hire and labour charges for shuttering with e=centering and necessary staging upto 4m. ;using approved stout props and thick hard wood polanks of approved thickness with required bracing for concrete slabs, beams, after completion of works. (a) 25 mm to 30 mm thick wooden shuttering as per decision and direction of Engineer-in-charge. (i) with out staging. (ii) With staging.	8m ² 62m ²	221.00/m ² 351.00/m ²	1768.00 21762.00
06.	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc. including supply of rods, intial straightening and removal of loose rust (in necessary), Cutting to requisite length, hoking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every inter-section, complete as per drawing and direction. (i) Tor steel/Mild steel (i) In ground floor.	6.60 Qtl.	6304.90/Qtl.	41612.00
07.	Brick work with 1 st class bricks in cement mortar (6:1) b) in superstructure In ground floor (i) In Foundation. (ii)In superstructure G.F.	2m ³ 6m ³	5253.00/m ³ 5478.00/m ³	10506.00 32868.00
08.	125 mm thick brick work with 1 st class bricks in cement mortar (4:1) (i) In Ground floor.	17m ²	726.00/m ²	12342.00
09.	M.S. or W.I.Ornamental grill of approved design joints continuously welded with M.S., W.I.Flats and bars of windows, railing etc. fitted and fixed with necessary screws and lugs. In ground floor.	0.86 Qtl.	8381/Qtl.	7208.00
10.	Earth work in filling in foundation trenches or plinth with good earth in layerfs not exccding 150 mm including watering and ramming etc. layer by layer complete. (i) With earth obtained from excavation of foundation.	2.50m ³	78.31/m ³	196.00

Contd.....(P).....(2).....

11.	With carried earth arranged by the contractor within a radius of 3Km including earth of carried earth.	2.50m ³	358.96/m ³	897.00
12.	Plaster (to wall, floor ceiling etc.) with sand and cement mortar including rounding off corners as directed.(i) With (1:4) cement mortar 10 mm thick.(Ceiling) (v) 6:1 cement mortar 20 mm thick(inside) (vi) G.F. 1:6 cement mortar 15 mm thick.	9m ² 61m ² 57m ²	136.00/m ² 173.00/m ² 150.00/m ²	1224.00 10553.00 8550.00
13.	Neat cement punning about 1.5 mm thick in wall, dado, window, sills, floor drain etc. in all floors about 1.5 mm thick.	14m ²	39.00/m ²	546.00
14	Artificial stone in floor, dado etc. with cement concrete (1:2:4) with stone chips laid in panels as directed 3mm thick topping, 35 mm thick.	9m ²	341.00/m ²	3069.00
15	M.S.gate as per approved design made of strong M.S.frame work intermediate stiffeners and round (sq. bar or angles M.S.sheet (not less then 14 gange) including necessary riveting, bolting, welding locking and hanging arrangements fitting and fixing complete as per direction of the E.I.C.	0.70 Qtl.	8661.00/Qtl.	6063.00
16.	White washing including cleaning and smoothening surface thoroughly (All floors) (Three coats) (on new works only)	65m ²	20.81/m ²	1353.00
17.	Acrylic exterior grade Acrylic acrylic primar (as per manufacturer's specification) including cleaning and smoothening of surface.(a) In Ground Floor.	51m ²	34.04/m ²	1736.00
18.	Protective and decorative acrylic exterior emulsion paint of approved quality after preparing the surface including scraping the same thoroughly (plastered or cement surface) as per manufacturer's specification. In ground floor iii) Two coats. In Ground floor.	51m ²	108.00/m ²	5508.00
19	Painting with best quality synthetic enamel paint (i) On steel or other metal surface.	12m ²	86.00/m ²	1032.00

Total Rs.236780.00

6/14/17

Executive Engineer
Directorate of Textiles (Sericulture)
West Bengal.